

Air/water heat pump NIBE \$2125 UK 1x230V





IHB EN 2212-1 631680

Table of Contents

1	Important information	4
	Safety information	. 4
	Symbols	4
	Marking	. 4
	Serial number	. 4
	Country specific information	. 5
	Inspection of the installation	. 6
	Compatible indoor modules (VVM) and control modules (SMO)	. 7
	Indoor module	. 7
	Control module	. 7
2	Delivery and handling	. 8
	Transport	. 8
	Assembly	. 9
	Condensation	. 11
	Supplied components	12
	Removing the side panel and top panel	. 13
	Installation of automatic gas separator	. 14
3	The heat pump design	. 17
	General	. 17
	Distribution box	. 20
	Sensor placement	. 21
4	Pipe connections	22
	General	. 22
	Symbol key	23
	Pipe coupling heating medium circuit	23
5	Electrical connections	25
	General	
	Accessibility, electrical connection	25
	Connections	. 26
6	Commissioning and adjusting	31
	Preparations	. 31
	Filling and venting	. 31
	Start-up and inspection	. 31
	Post adjustment and venting	
	Adjustment, charge flow	32
7	Control	33
	General	. 33
	I ED etetus	77

	Master control	33
	Control conditions	34
	Control - Heat pump EB101	35
8	Service	38
	Service actions	38
9	Servicing and maintenance	39
	Important	39
	General inspection	39
	Heating System	39
10	Disturbances in comfort	40
	Troubleshooting	40
	Alarm list	42
11	Accessories	44
12	Technical data	45
	Dimensions	45
	Sound levels	46
	Technical specifications	47
	Energy labelling	50
	Electrical circuit diagram	53
Ite	m register	57
Со	ntact information	63

NIBE S2125 Table of Contents 3

Important information

Safety information

This manual describes installation and service procedures for implementation by specialists.

The manual must be left with the customer.

Symbols

Explanation of symbols that may be present in this manual.



NOTE

This symbol indicates danger to person or machine.



Caution

This symbol indicates important information about what you should consider when installing or servicing the installation.



TIP

This symbol indicates tips on how to facilitate using the product.

Marking

Explanation of symbols that may be present on the product's label(s).



Fire hazard!



Read the User Manual.



Read the Installer Manual.




Disconnect the voltage supply before starting work.



Dangerous voltage.

Serial number

The serial number can be found on the rear cover and at the bottom on the side.





Caution

You need the product's (14 digit) serial number for servicing and support.

Country specific information

UNITED KINGDOM

This installation is subject to building regulation approval, notify the local Authority of intention to install.

Use only manufacturer's recommended replacement parts.

For more information see www.nibe.co.uk.



Benchmark places responsibilities on both manufacturers and installers. The purpose is to ensure that customers are provided with the correct equipment for their needs, that it is installed, commissioned and serviced in accordance with the manufacturers instructions by competent persons and that it meets the requirements of the appropriate Building Regulations. The Benchmark Checklist can be used to demonstrate compliance with Building Regulations and should be provided to the customer for future reference.

Installers are required to carry out the installation, commissioning and servicing work in accordance with the Benchmark Code of practice which is available from the Heating and Hotwater Industry Council who manage and promote the Scheme. Visit centralheating.co.uk for information.

Warranty and insurance information

Thank you for installing a new NIBE heat pump in your home.

NIBE heat pumps are manufactured in Sweden to the very highest standard so we are pleased to offer our customers a comprehensive guarantee.

The product is guaranteed for 24 months for parts and labour from the date of installation or 33 months from the date of manufacture, whichever is the shorter.

The NIBE guarantee is based on the unit being installed and commissioned by a NIBE accredited installer, serviced every year and the Benchmark documents completed. Where this condition is not met, any chargeable spare parts or components issued within the applicable guarantee period still benefit from a 12 month warranty from the date of issue by the manufacturer.

We recommend the installer completes and returns as soon as possible, your guarantee registration card or completes the guarantee form on the NIBE website www.nibe.co.uk

Electrical Supply

The heat pump must be permanently connected to a 230 V \sim 50 Hz supply.

All system components shall be of an approved type and all wiring to current I.E.E wiring regulations.

External wiring must be correctly earthed, polarised and in accordance with the relevant standards: Currently this is BS 7671.

Heating System

The installation of the heat pump should follow best practice as covered in the following:

BS 5449 Forced circulation hot water central heating systems for domestic premises.

BS 15450 Heating systems in buildings – Design of heat pump heating systems.

Inspection of the installation

Current regulations require the heating installation to undergo an installation inspection before it is commissioned. The inspection must be carried out by a suitably qualified person. In addition, fill in the page for information regarding the installation data in the User Manual.

<u> </u>	Description	Notes	Signature	Date
Heat	ting medium (page 22)			
	Automatic gas separator installed			
	System flushed			
	System vented			
	Particle filter			
	Shut-off and drain valve			
	Charge flow set			
Elec	tricity (page 25)			
	Fuses property			
	Safety breaker			
	Earth circuit-breaker			
	Heating cable type/effect			
	Fuse size, heating cable (F3)			
	Communication cable connected			
	S2125 addressed (only when cascade connection)			
	Cooling permitted			
	Connections			
	Main voltage			
	Phase voltage			
Misc	ellaneous			
	Condensation water pipe			
	Insulation for condensation water pipe, thickness (unless KVR 11 is used)			
	Warranty			
	Benchmark checklist			



NOTE

Check the connections, main voltage and phase voltage before powering up the heat pump, to prevent damage to the heat pump electronics.

Compatible indoor modules (VVM) and control modules (SMO)

	VVM S320	SM0 S40
S2125-8	X	X
S2125-12	X	X

	VVM 225	SM0 20	SM0 40
S2125-8	X	X	X
S2125-12		X	Х

Indoor module

VVM S320

Stainless steel, 1x230 V With T&P valve Part no. 069 199

VVM 225

Stainless steel, 1x230 V With T&P valve Part no. 069 232

Control module

SM0 S40

Control module Part no. 067 654

SMO 20

Control module Part no. 067 224

SMO 40

Control module Part no. 067 225

Delivery and handling

Transport

S2125 must be transported and stored vertically.



NOTE

Ensure that the heat pump cannot fall over during transport.

Check that the heat pump has not been damaged during transport.


LIFT FROM THE STREET TO THE SET UP LOCATION

If the base allows, the simplest thing is to use a pallet truck to move the S2125 to the set up location.



NOTE

The centre of gravity is offset to one side (see print on the packaging).



If S2125 needs to be transported across soft ground, such as a lawn, we recommend using a crane truck that can lift it to the installation location. When S2125 is lifted with a crane, the packaging must be untouched.

If a crane vehicle cannot be used the S2125 can be transported on an extended sack truck. S2125 must be taken from its heaviest side and two people are required to lift S2125.

LIFT FROM THE PALLET TO FINAL POSITIONING

Before lifting remove the packaging and the securing strap to the pallet.


Place lifting straps around each machine foot. Lifting from the pallet to the base requires four persons, one for each lifting strap.

SCRAPPING


When scrapping, the product is removed in reverse order. Lift by the bottom panel instead of a pallet!

Assembly

- Place the heat pump in a suitable location outdoors to prevent any risk of the refrigerant flowing in through ventilation openings, doors or similar openings in the event of a leak. It must also not constitute a hazard to people or property in any other way.
- If the heat pump is placed in a location where any refrigerant leak could accumulate, for example below ground level (in a dip or low-lying recess), the installation must satisfy the same requirements that apply for gas detection and the ventilation of engineering rooms. Requirements regarding sources of ignition must be applied where appropriate.
- Place S2125 outdoors on a solid level base that can take the weight, preferably a concrete foundation. If concrete slabs are used they must rest on asphalt or shingle.
- The lower edge of the evaporator must not be lower than the level of the average local snow depth. The base should be at least 70 mm tall.
- S2125 should not be positioned next to noise sensitive walls, for example, next to a bedroom.
- Also ensure that the placement does not inconvenience the neighbours.
- S2125 must not be placed so that recirculation of the outdoor air is possible. Recirculation entails reduced power and impaired efficiency.
- The evaporator must be sheltered from direct wind /, which negatively affects the defrosting function. Place S2125 protected from wind / against the evaporator.
- A small amount of water may drip from the drainage hole under S2125. Make sure that the water can run away by selecting a suitable material underneath S2125 (see section "Condensation").
- Care must be exercised so that the heat pump is not scratched during installation.




Do not place S2125 directly on the lawn or other non solid surface.



If there is a risk of snow slip from roof, a protective roof or cover must be erected to protect the heat pump, pipes and wiring.

INSTALLATION AREA

The distance between S2125 and the house wall must be at least 350 mm, but not more than 500 mm in locations that are exposed to the wind. The free space above S2125 must be at least 1,000 mm. The free space in front must be at least 1,000 mm for any future servicing.



^{*} The space behind must not exceed 500 mm in locations that are exposed to the wind.

Condensation

The condensate drain pan collects and leads away the condensation water.



NOTE

It is important to the heat pump function that condensation water is led away and that the drain for the condensation water run off is not positioned so that it can cause damage to the house. Condensation run-off should be checked regularly, especially during the autumn. Clean if necessary.

- The condensation water (up to 50 litres/24 hrs) that collects in the trough should be routed away by a pipe to an appropriate drain, it is recommended that the shortest outdoor stretch possible is used.
- The section of the pipe that can be affected by frost must be heated by the heating cable to prevent freezing.



TIP


Pipe with heating cable for draining the condensation water trough is not included.

To ensure the function, the accessory KVR 11 should be used.

- · Route the pipe downward from S2125.
- The outlet of the condensation water pipe must be at frost free depth.
- Use a water trap for installations where air circulation may occur in the condensation water pipe.
- · The insulation must seal against the bottom of the condensation water trough.


DRAINAGE OF CONDENSATION

Stone caisson




If the house has a cellar the stone caisson must be positioned so that condensation water does not affect the house. Otherwise the stone caisson can be positioned directly under the heat pump.

Gutter drainage




Route the pipe downward from S2125.

The condensation water pipe must have a water seal to prevent air circulation in the pipe.



If none of the recommended alternatives is used good lead off of condensation water must be assured.


Supplied components





1 x filterball (G1") (QZ2)

1 x flexible pipe with bend (WN1) 1 x flexible pipe (WN2) (Dimensions, flexible pipes DN25, G1")




4 x gaskets



1x non-return valve (RM1.2)

1 x automatic gas separator (HQ8)

Removing the side panel and top panel Undo the screws, lift off the top panel and the top insulation.




Installation of automatic gas separator

The automatic gas separator and the safety valve should always be installed as instructed below.


 Check that all O-rings are present and that they are undamaged. Lubricate them with soapy water or similar to make installation easier.

Press the gas separator into place. Fit the clip. Twist the clip to ensure that it fastens properly.


Place the bracket in position, parallel with the outer edge. Secure the bracket with a screw. Use a socket wrench, size 10 mm.




2. Assemble the parts of the safety valve. Ensure that the arrow for the outlet is pointing down, as illustrated.




3. Then fit the safety valve with the associated pipes. The safety vale must be at an angle of 45°. Fit the clip. Twist the clip to ensure that it fastens properly.




4. Install the non-return valve. Fit the clip. Twist the clip to ensure that it fastens properly.




5. Install the right-hand side of the metal box. The lug in the insulation must go into the round hole in the bracket.




6. Fit the left-hand side in the same way.




7. Check that both halves of the gas separator are properly in place, parallel with the edge of the heat pump.




8. Fit the cover. Secure with three screws. Two screws in the lid, on the right and left-hand sides, and one screw in the bottom.



9. Secure the gas separator to the heat pump using two screws, one at the top and one at the bottom.




10. Install the lid that conceals the safety valve.




11. Screw the flexible pipes into place. The flexible pipes can be installed angled straight back or down, depending on which of the pipe connections the 90° bend is in-

stalled on. Install the flexible pipes with a slight bend, so they can absorb any vibrations that would otherwise be propagated through the building.




12. Check that the venting opening is not covered with pipe insulation. Pipe insulation should extend as far as the coupling and must not cover the opening.




The heat pump design

General

S2125 (1x230V)





PIPE CONNECTIONS

Heating medium connection, supply (from S2125) XL1 XL2 Heating medium connection, return (to S2125)

Service connection, high pressure XL20 XL21 Service connection, low pressure

XL40 Connection, drain condensation water trough

HVAC COMPONENTS

FL2 Safety valve, heating medium HQ8 Automatic gas separator 1 RM1.2 Non-return valve1

Vent valve, heating medium QM20 WM5 Condensation water trough

SENSORS ETC.

BP1 High pressure pressostat BP2 Low pressure pressostat BP8 Low pressure transmitter BP9 High pressure sensor BT3 Temperature sensor, return BT12 Temperature sensor, condenser supply line BT14 Temperature sensor, hot gas BT15 Temperature sensor, fluid pipe Temperature sensor, evaporator BT16 BT17 Temperature sensor, suction gas BT28 Temperature sensor, ambient

Temperature sensor, suction gas evaporator

ELECTRICAL COMPONENTS

AA2 Base card

BT84

AA13 Triac board

CA1 Capacitor (1x230V) **EB10** Compressor heater

FQ14 Temperature limiter, compressor

GQ1 Fan **QA40** Inverter

Choke (1x230V) RA1

Terminal block (1x230V) Х6

COOLING COMPONENTS

EP1 Evaporator EP2 Condenser GQ10 Compressor HQ9 Particle filter HS1 Drying filter Expansion valve QN1 QN2 4-way valve Bypass valve QN4 RM1.1 Non-return valve

MISCELLANEOUS

PZ1 Type plate

PZ3 Serial number PZ4


Sign, pipe connections

UB1 Cable gland, incoming supply

Designations according to standard EN 81346-2.


¹ Enclosed (not factory-fitted).


Distribution box




ELECTRICAL COMPONENTS				
AA2	Base ca	ard		
	X1	Terminal block, incoming supply		
	X2	Terminal block, compressor supply		
	X5	Terminal block, external control voltage		
	X9	Terminal block, connection KVR		
	X21	Terminal block, Compressor blocking, Tariff		
	X22	Terminal block, communications		
	X23	Terminal block, communications		
	X24	Terminal block, fan		
	X27	Terminal block, expansion valve QN1		
F1	Fuse, o	perating 230V~, 4A		
F2	Fuse, o	perating 230V~, 4A		
F3	Fuse fo	or external heating cable, KVR, 250mA		
F4	Fuse, f	Fuse, fan, 4A		
FC1	Miniature circuit-breaker (Replaced with automatic protection (FB1) when installing accessory KVR 11.)			
S1	DIPswi	DIP switch, addressing heat pump during multi operation		
S2	DIP sw	itch, different options		
S3	Reset b	putton		

Sensor placement







Pipe connections

General

Pipe installation must be carried out in accordance with current norms and directives.

The pipe dimension should not be less than the recommended pipe diameter according to the table. However, each system must be dimensioned individually to manage the recommended system flows.

MINIMUM SYSTEM FLOWS

The installation must be dimensioned to manage at least the minimum defrosting flow at 100% pump operation, see table.

Air/water heat pump	Minimum flow during defrost- ing (100% pump speed (I/s)	Minimum re- commended pipe dimen- sion (DN)	Minimum re- commended pipe dimen- sion (mm)
S2125-8 (1x230V)			
S2125-8 (3x400V)	0.32	25	28
S2125-12 (1x230V)	0.32	23	20
S2125-12 (3x400V)			



NOTE

An undersized system can result in damage to the product and lead to malfunctions.

S2125 can only operate up to a return temperature of about $65\,^{\circ}\text{C}$ and an outgoing temperature of about $75\,^{\circ}\text{C}$ from the heat pump.

S2125 is not equipped with shut-off valves on the heating medium side, rather these must be installed to facilitate any future servicing. The return temperature is limited by the return line sensor.



NOTE

This installation is subject to building regulation approval, notify the local Authority of intention to install.



NOTE

Use only manufacturer's recommended replacement parts.

HARD WATER AREAS

Normally, there should not normally be any problem installing S2125 in hard water areas, as the operating temperature is $50-60^{\circ}$ C.

CLEANING THE CLIMATE SYSTEM

When the water heater and the climate system have been filled with water, S2125 must operate at maximum normal temperature for at least one hour. Thereafter the system must be drained of water and refilled.

Before installing the heat pump in an existing system, it is important that the system is properly flushed through.

Even if the heat pump is to be installed in a new system, the heat pump and system should be flushed.



NOTE

Ensure that cleaning agent has been removed from the entire system before adding inhibitor.

After flushing an inhibitor should be used for long-term anticorrosion protection.

NIBE Energy Systems Limited recommends water treatments (supplied by e.g. Fernox and Sentinel) specifically designed for heat pumps.

WATER VOLUMES

To avoid short operating times and to enable defrosting, a certain available water volume is required. For the optimum operation of S2125, a minimum available water volume of 120 litres is recommended. This applies separately to heating and cooling systems.



NOTE


The pipe installation must be flushed out before the heat pump is connected so debris cannot damage component parts.

Symbol key

•	•	
Symbol	Meaning	
X	Shut-off valve	
(b)	Circulation pump	
\Rightarrow	Expansion vessel	
×	Filterball	
P	Pressure gauge	
<u> </u>	Safety valve	
Σt	Trim valve	
₩	Reversing valve/shunt	
	Control module	
•	Air/water heat pump	
111111	Radiator system	
<u> </u>	Domestic hot water	
	Water heater	

Pipe coupling heating medium circuit

You can find a list of compatible products in the section "Compatible indoor modules (VVM) and control modules (SMO)".



There is a difference between connection to a control module compared with connection to an indoor module.

See the Installer Manual for the indoor module/control module.

The heat pump is vented automatically with the aid of the gas separator (HQ8). The gas separator closes automatically when the valve housing has been vented and filled with li-

Install as follows:

- · expansion vessel
- · pressure gauge
- · pressure relief valve
- · charge pump
- · shut-off valve

To facilitate any future servicing.

· enclosed filterball (QZ2)


Installed before connection "heating medium return" (XL2) (the lower connection) on the vacuum pump.

· reversing valve.

When connecting to the control module, and if the system is to be able to work with both the climate system and the hot water heater.

trim valve

When connecting to control module and hot water heater.



The image shows connection to the control module.


CHARGE PUMP

The charge pump (not included in the product) is powered and controlled from the indoor module/control module. It has a built-in frost protection function and, for this reason, must not be switched off when there is a risk of freezing.


At temperatures below +2 °C the charge pump runs periodically, to prevent the water from freezing in the charge circuit. The function also protects against excess temperatures in the charge circuit.

PRESSURE DROP, HEATING MEDIUM SIDE

The diagram shows the pressure drop on the heating medium side, including the gas separator.



PIPE INSULATION



All outdoor pipes must be insulated with at least 19 mm thick pipe insulation.

Electrical connections

General

- Electrical installation and wiring must be carried out in accordance with national provisions.
- Disconnect S2125 before insulation testing the house wiring.
- If a miniature circuit breaker is used, this must have at least triggering characteristic "C". See section "Technical specifications" for fuse size.
- If the building is equipped with an RCD, S2125 must be equipped with a separate one.
- For 230V~ 50Hz, the incoming supply must be 230V~ 50Hz via distribution box with fuses.
- The routing of cables for heavy current and signals should be made out through the cable glands on the heat pump's right-hand side, seen from the front.
- · Use a screened cable for communication.
- To prevent interference, sensor cables to external connections must not be laid close to high voltage cables.
- Connect the charge pump to the control module. See where the charge pump is to be connected in the Installer Manual for your control module.



NOTE

Electrical installation and any servicing must be carried out under the supervision of a qualified electrician. Disconnect the current using the circuit breaker before carrying out any servicing.



NOTE

Check the connections, main voltage and phase voltage before the product is started, to prevent damage to the heat pump electronics.



NOTE

The live external control must be taken into consideration when connecting.



NOTE

If the supply cable is damaged, only NIBE, its service representative or similar authorised person may replace it to prevent any danger and damage.



NOTE

Do not start the system before filling up with water. Components in the system could be damaged.

Accessibility, electrical connection

See section "Removing the side panel and top panel".

Connections


POWER CONNECTION

The enclosed cable (length 1.8 m) for incoming electricity is connected to terminal block X1. Outside the heat pump there is approx. 1.8 m of cable available.

Connection 1 x 230 V



At installation, install the screwed connection on the rear of the heat pump. The part of the screwed joint that tensions the cable must be tightened to a tightening torque above 3.5Nm.



TARIFF CONTROL




NOTE

All supply circuits must be disconnected, because the compressor and the control system may have separate power supplies.

If the control is to be powered separately from other components in the heat pump (e.g. for tariff connection), a separate operating cable must be connected to terminal block (X5).

If external control voltage is used during tariff control, a closing contact must be connected to connection X21:1 and X21:2 (compressor blocking) to prevent an alarm. Compressor blocking must be performed either on the indoor module/control module or on the air/water heat pump, not on both simultaneously.



Placement of labels




Caution


These labels should only be placed on the heat pump in those cases where the heat pump has a tariff connection with an external supply voltage.

Two labels should be placed on S2125. The labels are enclosed with the manuals.

The small label is placed on the outside of the side panel.




The large label is placed on the inside of the side panel, next to the insulation. See section "Removing the side panel and top panel".




CONNECTING EXTERNAL CONTROL VOLTAGE

When connecting external control voltage, remove the bridges from terminal block X5 (see image).



Connect external control voltage (230V~ 50Hz) to terminal block X5:L, X5:N and X5:PE (as illustrated).




COMMUNICATION

Software version

In order for S2125 to be able to communicate with indoor module (VVM)/control module (SMO), you may need to update to a more recent software version.

Disconnect the connections in S2125

When connecting communication to an indoor module/control module, you need to disconnect the connectors in S2125.



Connection to indoor module/control module

S2125 communicates with NIBE indoor modules/control modules via a screened three-core cable (max area 0.75 mm²) to terminal block X22:1–4.

For connection in the indoor module/control module:


See the Installer Manual for the indoor module/control module.

SMO 20


Cascade connection

For cascade connection, connect terminal block X23 with the next heat pump's terminal block X22.

SM0 S40



SMO 40



COOLING

S2125 can supply cooling with cooling supply down to +7°C.



DIP S1 position 4 must be changed to ON in order to run cooling

CONFIGURATION USING DIP SWITCH

The communication address for S2125 to the indoor module / control module is selected on the base board (AA2). DIP switch S1 is used for configuration of address and functions. For cascade operation with SMO for example, addressing is required. S2125 has the address 1 as standard. In a cascade connection all S2125 must have a unique address. The address is coded in binary.



NOTE

Only change the DIP switches position when the product is not powered.

DIP S1 position	Slave	Address	Default set-
(1/2/3)		(com)	ting
off / off / off	Slave 1	01	OFF
on / off / off	Slave 2	02	OFF
off / on / off	Slave 3	03	OFF
on / on / off	Slave 4	04	OFF
off / off / on	Slave 5	05	OFF
on / off / on	Slave 6	06	OFF
off / on / on	Slave 7	07	OFF
on / on / on	Slave 8	08	OFF

DIP S1 position	Setting		Default set- ting
4	ON	Permits cooling	OFF

DIP S2 position	Setting	Default setting
1	OFF	OFF
2	OFF	OFF
3	OFF	OFF
4	OFF	OFF

Switch S3 is the reset button that restarts control.

CONNECTING ACCESSORIES

Instructions for connecting accessories can be found in the installation instructions provided for the respective accessory. See section "Accessories" for a list of the accessories that can be used with S2125.

Commissioning and adjusting

Preparations



Caution

Check the miniature circuit-breaker (FC1). It could have tripped during transport.



NOTE

Do not start S2125 if there is a risk that the water in the system has frozen.



NOTE

At the time of commissioning, complete all relevant sections of the Benchmark Checklist located at the back of this document.

Completion of the Benchmark Checklist is a condition of warranty. For full terms and conditions of warranty, please see our website nibe.co.uk.

COMPRESSOR HEATER

S2125 is equipped with a compressor heater that heats the compressor before start-up and when the compressor is cold.

Compressor heater (EB10) is activated when the heat pump is connected to the supply voltage. The compressor needs to be heated up before starting for the first time. From the time the indoor module/control module is connected and a heating demand arises, it may take a while before the compressor reaches the permitted start value.



NOTE

The compressor heater must have been active for a while, prior to starting for the first time, until the discharge sensor (BT14) has reached its set temperature, see section "Start-up and inspection".

Filling and venting

Fill the heating system to the necessary pressure. The heat pump is equpped with an automatic venting valve, which closes when the heat pump is filled with liquid.

Start-up and inspection

- 1. Communication cable must be connected.
- 2. If cooling operation with S2125 is wanted, DIP switch S1 position 4 must be changed according to the description in section "Cooling".
- 3. Turn the isolator switch on.
- 4. Ensure that the S2125 is connected to the power source.
- 5. Check that fuse (FC1) is on.
- 6. Reinstall the removed panels and cover.
- After the power to S2125 has been switched on, and there is a compressor demand from the indoor module/control module, the compressor starts once it has warmed up.
- 8. Adjust the charge flow according to size. Also see section "Adjustment, charge flow".
- 9. Adjust menu settings via the indoor module/control module as necessary.
- Fill in "Inspection of the installation", in section "Important information".



NOTE

The live external control must be taken into consideration when connecting.

Post adjustment and venting

Air is initially released from the hot water and venting may be necessary. If bubbling sounds can be heard from the heat pump, the charge pump or radiators, the entire system requires further venting. When the system has stabilised (correct pressure and all air eliminated), the automatic heating control system can be set as required.

Adjustment, charge flow

For correct function of the heat pump over the entire year, the charge flow must be correctly adjusted.

Adjustment may be required, especially for charging a separate water heater. It is therefore recommended to have the option of adjusting the flow across the water heater using a trim valve.

- Recommendation if there is insufficient hot water and information message "high condenser out" during hot water charging: increase the flow
- 2. Recommendation if there is insufficient hot water and information message "high condenser in" during hot water charging: reduce the flow

Control

General

S2125 is equipped with an internal electronic controller that handles all functions necessary for operation of the heat pump, e.g. defrosting, stop at max/min temperature, connection of the compressor heater, and protective functions during operation.

The integrated control shows information via status-LEDs and can be used during servicing.

Under normal operating conditions the home owner does not need to have access to the controller.

S2125 communicates with the NIBE indoor module/control module, which means that all settings and measurement values from S2125 are adjusted and read off on the indoor module/control module.



Caution

The main product's software must be the latest

LED status

The base board (AA2) has a status LED for easy control and troubleshooting.

LED	State	Explanation		
PWR	Not lit	Base board without power		
(green)	Continuous light	Base board power on		
CPU	Not lit	CPU without power		
(green)	Flashes	CPU running		
	Continuous light	CPU not running correctly		
EXT COM (green)	Not lit	No communication with indoor module/control module		
(groon)	Flashes	Communication with indoor module/control module		
INT COM	Not lit	No communication with inverter		
(green)	Flashes	Communication with inverter		
DEFROST (green)	Not lit	Neither defrosting nor protection is active		
(green)	Flashes	Some protection is active		
	Continuous light	Defrosting in progress		
ERROR	Not lit	No errors		
(red)	Flashes	Info alarm (temporary), active		
	Continuous light	Continuous alarm, active		
K1, K2, K3, K4,	Not lit	Relay in de-energised position		
K5	Continuous light	Relay activated		
N-RELAY		No function		
COMPR. ON		No function		

LED	State	Explanation	
PWR-INV	Not lit	Inverter without power	
(green)	Continuous light	Inverter has power	

HARMONIC FILTER (RA1)

Harmonic filter (RA1) has a status LED for easy control and troubleshooting.

When the capacitor is in operation, LED 201 is lit with a steady light.

LED	State	Explanation
LED 201	Not lit	Capacitor disconnected
(red)	Continuous light	Capacitor connected

Master control

To control S2125, a NIBE indoor module/control module is required, which calls upon S2125 according to demand. All settings for S2125 are made via the indoor module/control module. It also shows the status and sensor values from S2125.

Description		Value	Parameter space
Cut-out value activation passive defrosting	°C	4	4 - 14
Start temperature BT16 to calculate index	°C	-3	-5 - 5
Permit fan de-icing	(1/0)	No	Yes / No
Permit silent mode	(1 / 0)	No	Yes / No
Permit defrost more often	(1 / 0)	No	Yes / No

Chapter 7 | Control **NIBE S2125** 33

Control conditions

CONTROL CONDITIONS DEFROSTING

- If the temperature of the evaporator sensor (BT16) is below
 the start temperature for the defrosting function, S2125
 counts the time to "active defrosting" for each minute
 that the compressor is running, to create a defrosting requirement.
- Time until "active defrosting" is shown in minutes on the indoor module / control module. Defrosting starts when this value is 0 minutes.
- "Passive defrosting" is started, if the compressor requirement has been fulfilled, at the same time as there is a defrosting requirement and the outdoor temperature
 (BT28) is greater than 4 °C.
- Defrosting occurs actively (with compressor on and fan off) or passively (with compressor off and fan on).
- If the evaporator is too cold, a "safety defrost" starts. This
 defrosting can start earlier than the normal defrosting. If
 the safety defrosting occurs ten times in a row, the
 evaporator (EP1) on S2125 must be checked, which is indicated by an alarm.
- If "de-icing fan" is activated in the indoor module/control
 module, "de-icing fan" starts at the next "active defrosting". "De-icing fan" removes the build-up of ice on the fan
 blades and the front fan grille.

34

Active defrosting:

- The four way valve shifts to defrosting.
- 2. The fan stops and the compressor continues to run.
- When defrosting is complete, the four-way valve switches back to heating operation. The compressor speed is locked for a short period.
- 4. The ambient temperature is locked and the high return temperature alarm is blocked for two minutes after defrosting.

Passive defrosting:

- If there is no compressor demand, passive defrosting can start.
- 2. The four-way valve does not shift.
- 3. Fan runs at high speed.
- 4. If there is a compressor demand, passive defrosting stops and the compressor starts.
- 5. When passive defrosting is complete, the fan stops.
- 6. The ambient temperature is locked and the high return temperature alarm is blocked for two minutes after defrosting.

Chapter 7 | Control NIBE S2125

Control - Heat pump EB101

S-SERIES - VVM S / SMO S

These settings are made on the display on the indoor module/control module.

Menu 7.3.2 - Installed heat pump

Here, you make specific settings for the installed heat pump.

Silent mode permitted

Setting range: on/off

Max. frequency 1

Setting range: 25 – 120 Hz

Max. frequency 2

Setting range: 25 – 120 Hz

Compressor phase

Setting range S2125 1 x 230 V: L1, L2, L3

Detect compressor phase

Setting range S2125 1 x 230 V: off/on

Current limit

Setting range S2125 1 x 230 V: off/on

Max. current

Setting range S2125 1 x 230 V: 6 - 32 A

blockFreq 1

Setting range: on/off

From frequency

Setting range: 25 - 117 Hz

To frequency

Setting range: 28 - 120 Hz

blockFreq 2

Setting range: on/off

From frequency

Setting range: 25 – 117 Hz

To frequency

Setting range: 28 - 120 Hz

Defrosting

Start manual defrosting

Setting range: on/off

Start temperature for defrost function

Setting range: -3 - 3 °C

Cut-out value activation passive defrosting

Setting range: 2 – 10 °C

Defrost more often

Alternatives: Yes / No

Silent mode permitted: Here, you set whether silent mode is to be activated for the heat pump. Please note that you now have the option to schedule when silent mode will be active.

The function should only be used for limited periods, because S2125 possibly may not reach its dimensioned output.

Detect compressor phase: This shows in which the phase the heat pump has detected whether you have S2125 230V~50Hz. Phase detection normally occurs automatically in connection with start-up of the indoor module/control module. This setting can be changed manually.

Current limitation: Here, you set whether the current limitation function will be activated for the heat pump, if you have S2125 230V~50Hz. During active function, you can limit the value of the maximum current.

BlockFreq 1: Here, you can select a frequency range within which the heat pump is not permitted to work. This function can be used if certain compressor speeds cause noise disturbance in the house.

BlockFreq 2: Here, you can select a frequency range within which the heat pump is not permitted to work.

Defrosting: Here, you can change the settings that affect the defrost function.

Start manual defrosting: Here, you can start "active defrosting" manually, if the function needs to be tested for servicing or if necessary. This can also be used to accelerate the start of "fan de-icing".

Start temperature for defrost function: Here, you set the temperature (BT16) at which the defrost function will start. The value must only be changed in consultation with the installer.

Cut-out value activation passive defrosting: Here, you set the temperature (BT28) at which "passive defrosting" will be activated. During passive defrosting, the ice is melted by the energy from the ambient air. The fan is active during passive defrosting. The value must only be changed in consultation with the installer.

Defrost more often: Here, you activate whether defrosting will occur more frequently than normal. This selection can be made if the heat pump receives an alarm due to build-up of ice during operation caused, for example, by snow.

NIBE S2125 Chapter 7 | Control 35

Menu 4.11.3 - Fan de-icing

Fan de-icing

36

Setting range: off/on

Continuous fan de-icing

Setting range: off/on

Fan de-icing: Here, you set whether the "fan de-icing" function will be activated during the next "active defrosting". This can be activated if ice/snow sticks to the fan, grille or fan cone, which may be noticed due to abnormal fan noise from \$2125.

"Fan de-icing" means that the fan, grille and fan cone are heated using hot air from the evaporator (EP1).

Continuous fan de-icing: There is the option to set recurring de-icing. In this case, every tenth defrosting will be "Fan de-icing". (This can increase annual energy consumption.)

Chapter 7 | Control NIBE S2125

F-SERIES - VVM / SMO

These settings are made on the display on the indoor module/control module.

Menu 5.11.1.1 - heat pump

Here, you make specific settings for the installed heat pump.

Silent mode permitted

Setting range: yes / no

Detect compressor phase

Setting range S2125 1 x 230 V: off/on

Current limit

Setting range: 6 - 32 A

Factory setting: 32 A

blockFreq 1

Setting range: yes / no

blockFreq 2

Setting range: yes / no

Defrosting

Start manual defrosting

Setting range: on/off

Start temperature for defrost function

Setting range: -3 - 3 °C

Factory setting: -3 °C

Cut-out value activation passive defrosting

Setting range: 2 - 10 °C

Factory setting: 4 °C

Defrost more often

Setting range: Yes / No

Silent mode permitted: Here, you set whether silent mode is to be activated for the heat pump. Please note that you now have the option to schedule when silent mode will be active.

The function should only be used for limited periods, because S2125 possibly may not reach its dimensioned output.

Detect compressor phase: This shows in which the phase the heat pump has detected whether you have S2125 230V~50Hz. Phase detection normally occurs automatically in connection with start-up of the indoor module/control module. This setting can be changed manually.

Current limitation: Here, you set whether the current limitation function will be activated for the heat pump, if you have S2125 230V~50Hz. During active function, you can limit the value of the maximum current.

BlockFreq 1: Here, you can select a frequency range within which the heat pump is not permitted to work. This function can be used if certain compressor speeds cause noise disturbance in the house.

BlockFreq 2: Here, you can select a frequency range within which the heat pump is not permitted to work.

Defrosting: Here, you can change the settings that affect the defrost function.

Start manual defrosting: Here, you can manually start an "active defrosting", if the function needs to be tested for servicing or if necessary. This can be justified together with "fan de-icing".

Start temperature for defrost function: Here, you set the temperature (BT16) at which the defrost function will start. The value must only be changed in consultation with the installer.

Cut-out value activation passive defrosting: Here, you set the temperature (BT28) at which "passive defrosting" will be activated. During passive defrosting, the ice is melted by the energy from the ambient air. The fan is active during passive defrosting. The value must only be changed in consultation with the installer.

Defrost more often: Here, you activate whether defrosting will occur more frequently than normal. This selection can be made if the heat pump receives an alarm due to build-up of ice during operation caused, for example, by snow.

Menu 4.9.7 - tools

Fan de-icing

Setting range: off/on

Continuous fan de-icing

Setting range: off/on

Fan de-icing: Here, you set whether the "fan de-icing" function will be activated during the next "active defrosting". This can be activated if ice/snow sticks to the fan, grille or fan cone, which may be noticed due to abnormal fan noise from \$2125.

"Fan de-icing" means that the fan, grille and fan cone are heated using hot air from the evaporator (EP1).

Continuous fan de-icing: There is the option to set recurring de-icing. In this case, every tenth defrosting will be "Fan de-icing". (This can increase annual energy consumption.)

NIBE S2125 Chapter 7 | Control 37

Service

Service actions



NOTE

Servicing should only be carried out by persons with the necessary expertise.

When replacing components on S2125 only replacement parts from NIBE may be used.



NOTE

If an electrical connection has been disconnected and is connected, ground must be checked using a suitable multimeter.



NOTE

An immersion heater without a temperature limiter is not allowed to be installed.



NOTE

After servicing, complete the relevant Service Interval Record section of the Benchmark Checklist located at the back of this document.

Completion of the Service Interval Record is a condition of warranty. For full terms and conditions of warranty, please see our website nibe.co.uk.

DRAINING THE CONDENSER

In the event of a prolonged power failure or similar, for example, the condenser in S2125 may need to be drained of water.



38

NOTE

There may be some hot water when draining the heating medium side/climate system. There is a risk of scalding.

- 1. Close the shut-off valves.
- 2. Release the pressure using the vent valve (QM20) on the automatic gas separator (HQ8).
- 3. Release the clip and pull out the non-return valve (RM1.2) on the heating medium connection, return (to S2125) (XL2).

TEMPERATURE SENSOR DATA

Return line (BT3), condenser supply (BT12), liquid line (BT15)

Temperature (°C)	Resistance (k0hm)	Voltage (VDC)
-10	56.20	3.047
0	33.02	2.889
10	20.02	2.673
20	12.51	2.399
30	8.045	2.083
40	5.306	1.752
50	3.583	1.426
60	2.467	1.136
70	1.739	0.891
80	1.246	0.691

Discharge sensor (BT14)

Temperature (°C)	Resistance (k0hm)	Voltage (V)
40	118.7	4.81
45	96.13	4.77
50	78.30	4.72
55	64.11	4.66
60	52.76	4.59
65	43.64	4.51
70	36.26	4.43
75	30.27	4.33
80	25.38	4.22
85	21.37	4.10
90	18.07	3.97
95	15.33	3.83
100	13.06	3.68
105	11.17	3.52
110	9.59	3.36
115	8.26	3.19
120	7.13	3.01

Evaporator sensor (BT16), ambient sensor (BT28), suction gas sensor (BT17) and suction gas, evaporator (BT84)

Temperature (°C)	Resistance (k0hm)	Voltage (VDC)
-40	43.34	4.51
-30	25.17	4.21
-20	15.13	3.82
-10	9.392	3.33
0	6.000	2.80
10	3.935	2.28
20	2.644	1.80
30	1.817	1.39
40	1.274	1.07

Chapter 8 | Service NIBE S2125

Servicing and maintenance

Important

The NIBE heat pump requires minimal maintenance but to ensure the continued efficient running of your heat pump and guarantee in the warranty period it is recommended that it is checked and serviced annually by a qualified engineer.

Any servicing must be carried out by a competent person.

When replacing a part on the appliance, use only spare parts supplied by NIBE.

If any electrical connections have been disconnected and re-connected, checks for earth continuity must be tested for with a suitable multimeter.

On completion the Benchmark service record should be completed.

General inspection

Check the following:

- Condition of casing
- 2. Check Inlet grille is not clogged with leaves
- 3. Check fan for any obstructions
- 4. Electrical supply connections
- 5. Water connections
- 6. Heating system pressure
- 7. Alarm log

Correct any fault before continuing.



NOTE

Before removing any covers or replacing parts the heat pump must be isolated from the mains electrical supply.

Heating System

- 1. Inspect start and stop temperatures. Correct if required.
- 2. Inspect heat curve (SMO & VVM only). Correct if required.
- Check the heating system flow temperatures, the difference should be between 5-10°C. Adjust flow if required.
- 4. Inspect the heat pump charge flow temperature difference against charge flow with graphs on page 24. Adjust if required.

<u>^</u>

NOTE

After servicing, complete the relevant Service Interval Record section of the Benchmark Checklist located at the back of this document.

Completion of the Service Interval Record is a condition of warranty. For full terms and conditions of warranty, please see our website nibe.co.uk.

Disturbances in comfort

In most cases, the indoor module/control module notes a malfunction (a malfunction can lead to disturbance in comfort) and indicates this with alarms and action instructions in the display.

Troubleshooting



NOTE

In the event of action to rectify malfunctions that require work within screwed hatches, the incoming supply electricity must be isolated at the safety switch by or under the supervision of a qualified electrician.



🕞 Caution

Alarms are acknowledged on the indoor module / control module (VVM / SMO).

If the operational interference is not shown in the display the following tips can be used:

BASIC ACTIONS

Start by checking the following:

- All supply cables to the heat pump are connected.
- · Group and main fuses of the accommodation.
- The property's earth circuit breaker.
- The heat pump's fuse / automatic protection. (FC1 / FB1, FB1 only if KVR is installed.)
- The indoor module's/control module's fuses.
- · The indoor module's/control module's temperature lim-
- That the air flow to S2125 is not blocked by foreign objects.
- That S2125 does not have any external damage.

S2125 DOES NOT START

- · There is no demand.
 - The indoor module/control module does not call on heating, cooling or hot water.
- · Compressor blocked due to the temperature conditions.
 - Wait until the temperature is within the product's working range.
- · Minimum time between compressor starts has not been
 - Wait for at least 30 minutes and then check if the compressor has started.
- · Alarm tripped.
 - Follow the display instructions.

S2125 NOT COMMUNICATING

- · Check that S2125 is correctly installed in the indoor module (VVM) or the control module (SMO).
- · Check that the communication cable is correctly connected and working.

LOW HOT WATER TEMPERATURE OR A LACK OF **HOT WATER**



Caution

The hot water is always set on the indoor module (VVM) or the control module (SMO).

This part of the fault-tracing chapter only applies if the heat pump is docked to the hot water heater.

- · Large hot water consumption.
 - Wait until the hot water has heated up.
- Incorrect hot water settings in indoor module or control
 - See the Installer Manual for the indoor module/control module.
- · Clogged particle filter.
 - Switch off the system. Check and clean the particle filter.

LOW ROOM TEMPERATURE

- · Closed thermostats in several rooms.
 - Set the thermostats to max in as many rooms as possible.
- · Incorrect settings in indoor module or control module.
 - See the Installer Manual for the indoor module/control module.
- · Air-filled radiators/underfloor heating coils.
 - Bleed the system.

HIGH ROOM TEMPERATURE

- Incorrect settings in indoor module or control module.
 - See the Installer Manual for the indoor module/control module.

ICE BUILD-UP IN THE FAN, GRILLE AND/OR FAN **CONE ON S2125**

- Activate "fan de-icing" in the indoor module/control module. Alternatively "continuous fan de-icing" if the problem recurs.
- · Check that the air flow across the evaporator is correct.

LARGE AMOUNT OF WATER BELOW S2125

- The accessory KVR 11 is required.
- If KVR 11 is installed, check that the water drainage flows freely.

ACTIVE DEFROSTING IS TERMINATED

There are several possible reasons for an active defrosting to end:

- If the temperature of the evaporator sensor has reached its stop value (normal stop).
- When defrosting has gone on for longer than 15 minutes.
 This may be due to too little energy in the heat source,
 too strong a wind effect on the evaporator and/or that
 the sensor on the evaporator is not correct and therefore displays too low a temperature (at cold outdoor air).
- When the temperature on the return line sensor, BT3, falls below 10 °C.
- If the temperature of the evaporator (BP8) falls below its lowest permitted value. After failing to defrost ten times, S2125 must be checked. This is indicated by an alarm.

Alarm list

Alarms VVM/SMO	Alarms S-series	Alarm text on the display	Description existing alarm	May be due to
(S2125)				
156 (80)	212	Low Ip cooling	5 repeated alarms for low low-pressure	Poor flow.
			within 4 hours.	Significant wind effect.
224 (182)	233	Fan alarm from heat pump	5 unsuccessful start attempt.	Fan blocked or not connected.
225 (8)	234	Exchange Sensors flow / return	Return is hotter than flow.	Connection, supply line return line switched around,
227 (34)	530	Sensor fault from heat pump	Sensor fault BT3.	Open-circuit or short-circuit on
227 (36)	531		Sensor fault BT12.	sensor input.
227 (38)	532		Sensor fault BT14.	
227 (40)	533		Sensor fault BT15.	
227 (42)	534		Sensor fault BT16.	
227 (44)	535		Sensor fault BT17.	
227 (46)	536		Sensor fault BT28.	
227 (50)	538		Sensor fault BP8.	
227 (52)	539		Sensor fault BP9.	
227 (56)	541		Sensor fault BT84.	
228 (2)	236	Unsuccessful defrosting	10 failed consecutive defrostings.	System temperature and/or flow too low.
				Insufficient available system volume.
				Significant wind effect.
229 (4)	237	Short run times for com-	Operation is stopped from the indoor sec-	Poor flow, poor heat transfer.
		pressor	tion after less than 5 minutes.	Incorrect settings for heating and/or hot water.
230 (78)	238	Hot gas alarm	3 repeated alarms for high discharge within 4 hours.	Disruption in the refrigerant circuit.
				Lack of refrigerant.
232 (76)	240	Low evaporation temp	5 repeated alarms for low evaporation	Lack of refrigerant.
			temperature within 4 hours.	Blocked expansion valve.
				Significant wind effect.
264 (203)	254	Communication fault to Inverter	Alarm 203 from heat pump for 20 seconds.	Poor connection between PCB and inverter.
				Inverter unpowered or broken.
298 (92)	494	Fault in inverter. Heating not working.	The inverter has tried to heat up the compressor, but has failed.	Defective inverter. Discharge sensor (BT14) has come loose from its mount.
300 (94)	495	Sensor BT14 or BP9 loose or defective	Sensor BT14 or BP9 has come loose or is otherwise defective.	The discharge sensor, BT14, or high pressure sensor, BP9, has come loose and is not giving correct measurement values.
341 (6)	291	Recurring safety defr.	10 repeated defrostings according to the protection conditions.	Poor airflow, e.g. because of leaves, snow or ice.
				Lack of refrigerant.
344 (72)	294	Recurring low pressure	5 repeated low pressure alarm within 4	Lack of refrigerant.
			hours.	Blocked expansion valve.
				Disruption in the refrigerant circuit.
346 (74)	295	Recurring high pressure	5 repeated high pressure alarm within 4 hours.	Clogged particle filter, air or stoppage in the heating medium flow.
				Poor system pressure.
400 (207)	314	Unspecified faults	Initiation fault, inverter.	The inverter is not compatible
400 (209)			The inverter is not compatible	
400 (211)			Configuration file missing.	
400 (213)			Charge error configuration.	

Alarms VVM/SM0	Alarms S-series	Alarm text on the display	Description existing alarm	May be due to
(S2125)	3-361163			
425 (108)	322	Persistent pressure switch or	2 repeated LP/HP/FQ alarms within 2.5	Poor heating medium flow.
		over-temperature alarm.	hours.	Lack of refrigerant.
				For FQ14, the following applies: High temperature 120 °C com- pressor peak.
427 (110)	323	Safety stop, inverter	Temporary fault in inverter, 2 times within 60 minutes.	Disruption in supply voltage.
429 (112)	324	Safety stop, inverter	Temporary fault in inverter, 3 times within 2 hours.	Disruption in supply voltage.
437 (120)	328	Mains disturbance	Temporary fault in inverter, 3 times within	Disruption in supply voltage.
			2 hours or continuously for 1 hour.	Incorrect connection in the inverter's terminal block X1.
439 (122)	329	Overheated inverter	The inverter has temporarily reached max	Poor cooling of inverter.
			working temperature, due to poor cooling 3 times within 2 hours or continuously for 1 hour.	Defective inverter.
441 (124)	330	Current too high	Current to inverter too high, 3 times within	Too high current to inverter.
			2 hours or continuously for 1 hour.	Low supply voltage.
443 (126)	331	Overheated inverter	The inverter has temporarily reached max	Poor cooling of inverter.
			working temperature, due to poor cooling 3 times within 2 hours or continuously for 1 hour.	Defective inverter.
447 (130)	333	Phase failure	Compressor phase is missing, 3 times	Disruption in supply voltage.
			within 2 hours or continuously for 1 minute.	Incorrectly connected compressor cable.
449 (132)	334	Failed compressor starts	Compressor does not start when required,	Defective inverter.
			3 times within 2 hours.	Defective compressor.
453 (136)	336	High current load, com-	The output current from the inverter to	Disruption in supply voltage.
		pressor	the compressor has been temporarily too high 3 times within 2 hours or continu-	Poor heating medium flow.
			ously for 1 hour.	Defective compressor.
455 (138)	337	High power load, compressor	The power output from the inverter has been too high 3 times within 2 hours or	Disruption in supply voltage.
			continuously for 1 hour.	Poor heating medium flow.
				Defective compressor.
501 (184)	353	Failed start, no pressure diff.	The pressure difference between BP9 and BP8 has been too low at compressor start 3 times within 30 minutes.	BP9.
			o unies within 50 minutes.	The compressor does not compress the refrigerant sufficiently.
				Compressor breakdown.
503 (186)	354	Compressor speed too low	Compressor speed below lowest permitted speed.	The inverter's safety function reduces the speed outside of the compressor's working range.
523	418	Low defrosting flow	The flow is low. Check particle filter and	Clogged particle filter.
			pump.	Defective circulation pump (charge pump).
				Pressure drop in the heating system is too large.
589 (216)	437	Incorrect PCBA in heat pump. Change to a new PCBA suitable for S2125.	The heat pump has the wrong base board.	The base board has been replaced with a base board for F2120.

Accessories

Detailed information about the accessories and complete accessories list available at www.nibe.co.uk.

Not all accessories are available on all markets.

CONDENSATION WATER PIPE

Condensation water pipe, different lengths.

KVR 11-10

1 metres Part no. 067 823

KVR 11-30

3 metres Part no. 067 824

KVR 11-60


44

6 metres Part no. 067 825


Chapter 11 | Accessories NIBE S2125

Technical data

Dimensions



Sound levels



S2125 is usually placed next to a house wall, which gives a directed sound distribution that has to be taken into consideration. Accordingly, when setting up, you should always attempt to select the side that faces the least sound-sensitive neighbouring area.

The sound pressure levels are further affected by walls, bricks, differences in ground level, etc and should therefore only be seen as guide values.


		Sound power 1			S	ound pr	essure	at dista	nce (m)	2		
			1	2	3	4	5	6	7	8	9	10
S2125-8	Nominal sound value	49	44	38	34.5	32	30	28.5	27	26	25	24
	Max. sound value	55	50	44	40.5	38	36	34.5	33	32	31	30
	Max. sound value, silent mode	50	45	39	35.5	33	31	29.5	28	27	26	25
S2125-12	Nominal sound value	49	44	38	34.5	32	30	28.5	27	26	25	24
	Max. sound value	59	54	48	44.5	42	40	38.5	37	36	35	34
	Max. sound value, silent mode	54	49	43	39.5	37	35	33.5	32	31	30	29

 $^{^{\}rm 1}~$ Sound power level, $\rm L_W(A),$ according to EN12102


² Sound pressure calculated according to directivity factor Q=4

Technical specifications

WORKING RANGE, HEATING



WORKING RANGE, COOLING




During shorter time it is allowed to have lower working temperatures on the water side, e.g. during start up.


POWER DURING HEATING OPERATION

Maximum and minimum capacity during continuous operation. Defrosting is not included.

S2125-8




S2125-12



POWER DURING COOLING OPERATION

Maximum and minimum capacity during continuous operation.



S2125		8	12
Voltage		1 x 230 V	1 x 230 V
Output data according to EN 14 511, partial load ¹			
Heating	-7 / 35 °C	4.72 / 1.72 / 2.82	7.23 / 2.73 / 2.65
Capacity / power input / COP (kW/kW/-) at nominal flow	2 / 35 °C	3.20 / 0.72 / 4.44	3.67 / 0.85 / 4.33
Outdoor temp: / Supply temp.	2 / 45 °C	2.95 / 0.87 / 3.39	3.46 / 1.02 / 3.40
	7/35 °C	3.15 / 0.69 / 5.18	3.67 / 0.70 / 5.21
	7 / 45 °C	2.97 / 0.76 / 3.90	3.35 / 0.85 / 3.91
Cooling	35 / 7 °C	6.69 / 2.41 / 2.77	6.69 / 2.41 / 2.77
Capacity / power input / EER (kW/kW/-) at maximum flow	35 / 18 °C	8.68 / 2.60 / 3.34	8.68 / 2.60 / 3.34
Outdoor temp: / Supply temp.			
SCOP according to EN 14825			
Nominal heat output (P _{designh}) average climate 35 °C / 55 °C (Europe)	kW	5.33 / 5.30	6.80 / 7.60
Nominal heat output (P _{designh}) cold climate 35 °C / 55 °C	kW	5.40 / 5.20	8.40 / 8.40
Nominal heat output (P _{designh}) warm climate 35 °C / 55 °C	kW	5.50 / 5.20	7.00 / 7.45
SCOP average climate, 35 °C / 55 °C (Europe)		5.00 / 3.70	5.00 / 3.80
SCOP cold climate, 35 °C / 55 °C		4.10 / 3.20	4.20 / 3.40
SCOP warm climate, 35 °C / 55 °C		6.30 / 4.50	6.30 / 4.60
Energy rating, average climate ²			
The product's room heating efficiency class 35 °C / 55 °C ³		A+++ / A++	A+++ / A+++
The system's room heating efficiency class 35 °C / 55 °C ⁴		*	/ A+++
Electrical data			
Rated voltage		230 V ~ 50 Hz	230 V ~ 50 Hz
Rated current, heat pump	A _{rms}	-	_
Max. power, fan	W	30	50
Fuse	A _{rms}	16	20
Enclosure class	rms		24
Refrigerant circuit		11 -	27
Type of refrigerant		D2	90
GWP refrigerant			70 3
Volume	ka		.8
Type of compressor	kg		ary
CO ₂ -equivalent (The cooling circuit is hermetically sealed.)	t		024
Cut-out value pressure switch HP (BP1)	MPa		15
Difference pressostat HP	MPa		45
Cut-out value pressure switch LP (BP2)	MPa		45 03
Difference pressostat LP	MPa MPa		10
Airflow	МРа	0.	10
Max airflow	m³/h	2,400	2,950
Working area	111-711	2,400	2,730
Min./max. air temperature, heating	°C	25	/ 38
Min./max. air temperature, neating	°C		⁷ 43
Defrosting system			e cycle
Heating medium circuit		Revers	e cycle
Max system pressure heating medium	MPa	0.45	(4.5)
Cut-off pressure, heating medium			(2.5)
Recommended flow interval, heating operation	MPa I/s	0.08 - 0.32	0.12 - 0.48
Min. design flow, defrosting (100% pump speed)	I/s		0.12 - 0.48 32
Min. design flow, derrosting (100% pump speed) Min./max. HM temp, continuous operation	°C		52 / 75
Connection heating medium S2125	U		nal thread
			nal thread
Connection heating medium flex pipe Min recommended pipe dimension (system)	DN (mm)	25	
Min. recommended pipe dimension (system) Dimensions and weight	(וווווו) אום	251	,20J
Width	mm	11	70
	mm		30 20
Depth Lisiaht	mm		
Height Weight	mm	-	156
Weight	kg	156	156
Miscellaneous		044.000	044.040
Part no.		064 220	064 218

 $^{1\ \ \}text{Power statements including defrosting according to EN 14511 at heating medium supply corresponding to DT=5\ K\ at\ 7\ /\ 45.}$

² The reported efficiency of the package also takes the controller into account. If an external supplementary boiler or solar heating is added to the package, the overall efficiency of the package should be recalculated.

 $^{^{\}rm 3}$ Scale for the product's room heating efficiency class A++ to $\,$ G. Control module model SMO S

 $^{^4\,}$ Scale for the system's room heating efficiency class A+++ to G. Control module model SMO S

Energy labelling INFORMATION SHEET

Supplier		NII	3E
Model		S2125-8	S2125-12
Temperature application	°C	35 / 55	35 / 55
Seasonal space heating energy efficiency class, average climate		A+++ / A++	A+++ / A+++
Rated heat output (P _{designh}), average climate	kW	5.3 / 5.3	6.8 / 7.6
Annual energy consumption space heating, average climate	kWh	2,196 / 2,939	2,835 / 4,102
Seasonal space heating energy efficiency, average climate	%	196 / 146	195 / 150
Sound power level L _{WA} indoors	dB	-	-
Rated heat output (P _{designh}), cold climate	kW	5.4 / 5.2	8.4 / 8.4
Rated heat output (P _{designh}), warm climate	kW	5.5 / 5.2	7.0 / 7.5
Annual energy consumption space heating, cold climate	kWh	3,238 / 4,055	4,990 / 6,189
Annual energy consumption space heating, warm climate	kWh	1,161 / 1,570	1,494 / 2,180
Seasonal space heating energy efficiency, cold climate	%	161 / 123	163 / 131
Seasonal space heating energy efficiency, warm climate	%	250 / 174	247 / 180
Sound power level L _{WA} outdoors	dB	49	49

DATA FOR ENERGY EFFICIENCY OF THE PACKAGE

Model		S2125-8	S2125-12
Control module model		SM0 S	SMO S
Temperature application	°C	35 / 55	35 / 55
Controller, class		V	' I
Controller, contribution to efficiency	%	4.	0
Seasonal space heating energy efficiency of the package, average climate	%	200 / 150	199 / 154
Seasonal space heating energy efficiency class of the package, average climate		A+++ / A+++	A+++ / A+++
Seasonal space heating energy efficiency of the package, cold climate	%	165 / 127	167 / 135
Seasonal space heating energy efficiency of the package, warm climate	%	254 / 178	251 / 184

The reported efficiency of the package also takes the controller into account. If an external supplementary boiler or solar heating is added to the package, the overall efficiency of the package should be recalculated.


TECHNICAL DOCUMENTATION


Model				S2125-8				
Type of heat pump		Brine	vater ust-water e-water r-water					
Low-temperature heat pump		Yes	No No					
Integrated immersion heater for additional hea	t	☐ Yes	No					
Heat pump combination heater		Yes	No No					
Climate		X Aver	age 🔲	Cold Warm				
Temperature application			um (55°C)	☐ Low (35°C)				
Applied standards		+		/ EN12102				
Rated heat output	Prated	5,3	kW	Seasonal space heating energy efficiency	η_s	146	%	
Declared capacity for space heating at part load Tj	d and at ou	utdoor ten	perature	Declared coefficient of performance for space outdoor temperature Tj	heating at	part load	and at	
Tj = -7 °C	Pdh	4.6	kW	Tj = -7 °C	COPd	2.19	-	
Tj = +2 °C	Pdh	2.8	kW	Tj = +2 °C	COPd	3.77	-	
Tj = +7 °C	Pdh	2.1	kW	Tj = +7 °C	COPd	4.75	-	
Tj = +12 °C	Pdh	2.3	kW	Tj = +12 °C	COPd	5.70	-	
Tj = biv	Pdh	4.6	kW	Tj = biv	COPd	2.19	-	
Tj = TOL	Pdh	4.8	kW	Tj = TOL	COPd	2.21	-	
Tj = -15 °C (if TOL < -20 °C)	Pdh		kW	Tj = -15 °C (if TOL < -20 °C)	COPd		-	
Bivalent temperature	T _{biv}	-10	°C	Min. outdoor air temperature	TOL	-10	°C	
Cycling interval capacity	Pcych		kW	Cycling interval efficiency	COPcyc		-	
Degradation coefficient	Cdh	0.97	-	Max supply temperature	WTOL	65	°C	
Power consumption in modes other than active	e mode			Additional heat				
Off mode	P _{OFF}	0.008	kW	Rated heat output	Psup	0.0	kW	
Thermostat-off mode	P _{TO}	0.013	kW					
Standby mode	P _{SB}	0.011	kW	Type of energy input		Electric		
Crankcase heater mode	P _{CK}	0.005	kW					
Other items								
Capacity control		Variable		Rated airflow (air-water)		2,400	m³/h	
Sound power level, indoors/outdoors	L _{WA}	- / 49	dB	Nominal heating medium flow			m³/h	
Annual energy consumption	Q _{HE}	2,939	kWh	Brine flow brine-water or water-water heat pumps			m ³ /h	
Contact information	NIBE En	nergy Systems – Box 14 – Hannabadsvägen 5 – 285 21 Markaryd – Sweden						


Model				\$2125-12			
Type of heat pump	vater ust-water -water r-water						
Low-temperature heat pump		Yes	No				
Integrated immersion heater for additional heat	:	Yes	No No				
Heat pump combination heater		Yes	No No				
Climate		X Avera	age \square	Cold Warm			
Temperature application		+	um (55°C)				
Applied standards		_		1 /EN12102			
Rated heat output	Prated	7,6	kW	Seasonal space heating energy efficiency	η_s	150	%
Declared capacity for space heating at part load Tj	l and at ou	utdoor tem	perature	Declared coefficient of performance for space outdoor temperature Tj	heating at	part load	and at
Tj = -7 °C	Pdh	6.7	kW	Tj = -7 °C	COPd	2.17	-
Tj = +2 °C	Pdh	4.2	kW	Tj = +2 °C	COPd	3.83	-
Tj = +7 °C	Pdh	2.7	kW	Tj = +7 °C	COPd	5.12	-
Tj = +12 °C	Pdh	2.4	kW	Tj = +12 °C	COPd	5.87	-
Tj = biv	Pdh	7.6	kW	Tj = biv	COPd	2.11	_
Tj = TOL	Pdh	7.6	kW	Tj = TOL	COPd	2.11	-
Tj = -15 °C (if TOL < -20 °C)	Pdh		kW	Tj = -15 °C (if TOL < -20 °C)	COPd		-
Bivalent temperature	T _{biv}	-10	°C	Min. outdoor air temperature	TOL	-10	°C
Cycling interval capacity	Pcych		kW	Cycling interval efficiency	COPcyc		-
Degradation coefficient	Cdh	0.97	-	Max supply temperature	WTOL	65	°C
Power consumption in modes other than active	mode			Additional heat			
Off mode	P _{OFF}	0.008	kW	Rated heat output	Psup	0	kW
Thermostat-off mode	P _{TO}	0.013	kW				
Standby mode	P _{SB}	0.011	kW	Type of energy input		Electric	
Crankcase heater mode	P _{CK}	0.005	kW				
Other items							
Capacity control		Variable		Rated airflow (air-water)		2,900	m³/h
Sound power level, indoors/outdoors	L _{WA}	- / 49	dB	Nominal heating medium flow			m³/h
Annual energy consumption	Q _{HE}	4,102	kWh	Brine flow brine-water or water-water heat pumps			m³/h
Contact information	NIBE En	ergy Syste	ms – Box	14 – Hannabadsvägen 5 – 285 21 Markaryd – Sw	eden		


Electrical circuit diagram

1 X 230 V









Item register

A	E
Accessories, 44	Electrical circuit diagram, 53
Adjustment, charge flow, 32	Electrical connections, 25
Alarm list, 42	Communication, 28
Areas with hard water, 22	Configuration using DIP switch, 30
Assembly, 9	Connecting accessories, 30
,	Connections, 26
B	General, 25
Basic actions, 40	Power connection, 26
C	Tariff control, 27
Charge pump, 23	Energy labelling, 50
Cleaning the climate system, 22	Data for energy efficiency of the package, 50
Commissioning and adjusting, 31	Information sheet, 50
Adjustment, charge flow, 32	Technical documentation, 51
Filling and venting the heating medium system, 31	F
Post adjustment and bleeding, 31	Filling and venting the heating medium system, 31
Preparations, 31	G
Start-up and inspection, 31	
Communication, 28 Compatible indoor modules (VVM) and control modules	General, 25
(SMO), 7	Н
Component placement	Heat pump settings – Menu 7.3.2, 35, 37
Sensor placement, 21	High room temperature, 40
Compressor heater, 31	I
Condensation, 11	Ice build-up in the fan, grille and/or fan cone, 40
Configuration using DIP switch, 30	Important information, 4
Connecting accessories, 30	Compatible indoor modules (VVM) and control modules
Connecting external control voltage, 28	(SMO), 7
Connections, 26	Control module, 7
Connecting external control voltage, 28	Country specific information, 5
Control, 33	Indoor module, 7
Control conditions, 34	Inspection of the installation, 6
Control conditions, defrosting, 34	Safety information, 4
Control – Heat pump EB101, 35	Indoor module, 7
Control - Introduction, 33	Inspection of the installation, 6
General, 33	Installation area, 10
LED status, 33	Installing the installation
Control conditions, 34	Symbol key, 23
Control conditions defrosting, 34	L
Control - Heat pump EB101, 35	Large amount of water below S2125, 41
Control – Heat pump EB101	LED status, 33
Heat pump settings – Menu 7.3.2, 35, 37 Control - Introduction, 33	Low hot water temperature or no hot water, 40
Master control, 33	Low room temperature, 40
Control module, 7	M
Country specific information, 5	Marking, 4
D	Master control, 33
	P
Delivery and handling, 8	Pipe connections, 22
Assembly, 9 Compressor heater, 31	Charge pump, 23
Condensation, 11	General, 22
Installation area, 10	Areas with hard water, 22
Supplied components, 12	Cleaning the climate system, 22
Transport, 8	Pipe coupling, heating medium, 23
Dimensions, 45	Symbol key, 23
Disruption to comfort	Water volumes, 22
Temperature sensor data, 38	Pipe coupling, heating medium, 23
Distribution box, 20	Post adjustment and bleeding, 31
Disturbances in comfort, 40	Power connection, 26
Alarm list, 42	Preparations, 31
Troubleshooting, 40	S
Draining the heat pump, 38	S2125 does not start 40

NIBE S2125 Item register 57

```
S2125 not communicating, 40
Safety information, 4
  Marking, 4
  Serial number, 4
  Symbols, 4
  Warranty information, 5
Sensor placement, 21
Serial number, 4
Service, 38
  Service actions, 38
Service actions, 38
Service measures
  Draining the heat pump, 38
Sound levels, 46
Start-up and inspection, 31
Supplied components, 12
Symbol key, 23
Symbols, 4
Т
Tariff control, 27
Technical data, 45
  Dimensions, 45
  Electrical circuit diagram, 53
  Sound pressure levels, 46
  Technical Data, 47
Technical Data, 47
Temperature sensor data, 38
The heat pump design, 17
  Component locations, 17
  List of components, 17
The heat pump's design
  Distribution box, 20
Transport, 8
Troubleshooting, 40
  Basic actions, 40
  High room temperature, 40
  Ice build-up in the fan, grille and/or fan cone, 40
  Large amount of water below S2125, 41
  Low hot water temperature or no hot water, 40
  Low room temperature, 40
  S2125 does not start, 40
  S2125 not communicating, 40
```

W

Warranty information, 5

58 Item register NIBE S2125

AIR TO WATER HEAT PUMP COMMISSIONING CHECKLIST

This Commissioning Checklist is to be completed in full by the competent person who commissioned the heat pump and associated equipment as a means of demonstrating compliance with the appropriate Building Regulations and then handed to the customer to keep for future reference. Failure to install and commission this equipment to the manufacturer's instructions may invalidate the warranty but does not affect statutory rights. **Customer Name** Address Telephone Number Heat Pump Make and Model Heat Pump Serial Number Commissioned by (print name) Certified Operative Reg. No. Company Name & Address Commissioning Date Telephone No. **Building Regulations Notification Number** (if applicable) [2] **CONTROLS - SYSTEM AND HEAT PUMP** Tick the appropriate boxes if applicable 1. Time & Temperature Room Thermostat & Programmable Load/Weather **Optimum Start** Control to Heating Programmer/Timer Roomstat Compensation Control 2. Time & Temperature Cylinder Thermostat & Combined with Heat Control to Hot Water Programmer/Timer pump main controls 3. Heating Zone Valves Fitted Not Required 4. Hot Water Zone Valves Fitted Not Required 5. Thermostatic Radiator Valves Fitted Not Required 6. Heat Pump Safety Interlock Provided 7. Outdoor Sensor Fitted Not Required 8. Automatic Bypass System Fitted Not Required 9. Buffer Vessel Fitted Yes No 🗌 If YES Volume [Litres **ALL SYSTEMS** The heating system has been filled and pressure tested Yes Expansion vessel for heating is sized, fitted & charged in accordance with manufacturer's instructions Yes The heat pump is fitted on a solid/stable surface capable of taking its weight Yes The system has been flushed and cleaned in accordance with BS7593 and heat pump manufacturer's instructions Yes What system cleaner was used? What inhibitor was used? Qty litres[Is the system adequately frost protected? **OUTDOOR COLLECTOR** Are all external pipeworks insulated? Yes Yes Is the fan free from obstacles and operational? Has suitable consideration been made for waste water discharge? Yes **CENTRAL HEATING MODE Heating Flow Temperature** P∘C Heating Return Temperature DOMESTIC HOT WATER MODE Is the heat pump connected to a hot water cylinder? Unvented Vented ☐ Thermal Store Not Connected Hot water has been checked at all outlets Yes ADDITIONAL SYSTEM INFORMATON Additional heat sources connected Gas Roiler Oil Boiler Electric Heater Other **ALL INSTALLATIONS** The heating, hot water and ventilation systems complies with the appropriate Building Regulations Yes All electrical work complies with the appropriate Regulations Yes The heat pump and associated products have been installed and commissioned in accordance with the manufacturer's instructions The operation of the heat pump and system controls have been demonstrated to the customer Yes The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer Yes Commissioning Engineer's Signature Customer's Signature (To confirm demonstration of equipment and receipt of appliance instructions)

Notes: [1] Installers should be members of an appropriate Competent Persons Scheme. [2] All installations in England and Wales must be notified to Local Area Building Control (LABC) either directly or through a Competent Persons Scheme. A Building Regulations Compliance Certificate will then be issued to the customer. [3] May be required for systems covered by G3 Regulations



Service Record

It is recommended that your heating system is serviced regularly and that the appropriate Service Interval Record is completed.

Service Provider
Before completing the appropriate Service Interval Record below, please ensure you have carried out the service as described in the manufacturer's instructions.

Always use the manufacturer's specified spare part when replacing controls.

Service 1 Date:	Service 2 Date:	
Engineer Name:	Engineer Name:	
Company Name:	Company Name:	
Telephone No.	Telephone No.	
Operative ID No.	Operative ID No.	
Comments:	Comments:	
Signature:	Signature:	
Service 3 Date:	Service 4 Date:	
Engineer Name:	Engineer Name:	
Company Name:	Company Name:	
Telephone No.	Company Name: Telephone No.	
Operative ID No.	Operative ID No.	
Comments:	Comments:	
Signature:	Signature:	
<u>J.G. Hattares</u>	- January	
Service 5 Date:	Service 6 Date:	
Engineer Name:	Engineer Name:	
Company Name:	Company Name:	
Telephone No.	Telephone No.	
Operative ID No.	Operative ID No.	
Comments:	Comments:	
		
Signature:	Signature:	
Service 7 Date:	Service 8 Date:	
Engineer Name:	Engineer Name:	
Company Name:	Company Name:	
Telephone No.	Telephone No.	
Operative ID No.	Operative ID No.	
Comments:	Comments:	
Signature:	Signature:	
Service 9 Date:	Service 10 Date:	
Engineer Name:	Engineer Name:	
Company Name:	Company Name:	
Telephone No.	Telephone No.	
Operative ID No.	Operative ID No.	
Comments:	Comments:	
Signature:	Signature:	

NIBE Energy Systems Ltd 3C Broom Business Park, Bridge Way, S41 9QG Chesterfield Tel: +44 (0)330 311 2201 info@nibe.co.uk nibe.co.uk

This is a publication from NIBE Energy Systems. All product illustrations, facts and data are based on the available information at the time of the publication's approval.

NIBE Energy Systems makes reservations for any factual or printing errors in this publication.

